

CT1 placement determines the L1 phase for the entire system; including the Hub, ESS, and PV circuits.


Main Panel





EVOLVE MODELS: E5 / LFP MAX Wiring Quick Guide

# **Partial Home Backup**



Backup Panel




CT1 placement determines the L1 phase for the entire system; including the Hub, ESS, and PV circuits.





EVOLVE MODELS: E5 / LFP MAX
Wiring Quick Guide

# **Whole Home Backup**



Main Panel

# Register Device Online

C-----

The EMC UID and S/N are found on the label inside the Evolve Hub.

1 Login via web browser.

log in

Installer@eguanatech.com

For FLEET INSTALLER USERS only

On-board (register) customer and device.

fleet.eguanatech.com/fleet\_installer\_users/sign\_in

Add New Device

installer dashboard devices

ces commissioning profiles customers blo

The following fields require completion before system commissioning.

**Customer info:** email, name (first/last), country, state. **Device info:** UID, S/N, total inverter AC capacity kW (PV only), number of battery modules.

**Device location:** country, state

 $\ast$  For time of use (TOU) applications, refer to special instructions provided by the manufacturer at time of order.

\* Gateway reports to cloud in 5 minute intervals. Allow up to 15 minutes for initial data.


**Add Device** 


- Internet connection is wired ethernet. Wifi or other network options are not supported.
- Power up the Evolve ESS.
  - 1. Turn ON all power switches on the battery modules.
  - 2. Press the SW button on the master battery module.
  - 2. Turn ON the battery disconnect (DC).
  - 3. Turn ON the Evolve Hub breaker at the main panel.
  - \*System commissioning is preconfigured for self-supply algorithm
- Log into Fleet.Eguanatech.com/Fleet\_installer\_user/sign\_in
  - 1. Click on Devices.
  - 2. Click on customer UID that was recently onboarded.
  - 2. Go to Status Tab, confirm internet connection is established, will have a green Ethernet symbol.
  - 3. Go to PCS status in status tab ,open Latest PCS reading and confirm Inverter is communicating .
  - 4. Confirm "state" field is populated with information.
- 5 Configure the Gateway for ESS


Log into Fleet.Eguanatech.com/ Fleet\_installer\_user/sign\_in

- 1. Click on Devices.
- 2. Click on Customer UID that was recently onboarded.
- 3. Go to Configuration tab , system configuration and click view and edit.
- 4. Open Configuration settings.
- 5. Configure timezone , algorithm mode , EMC interconnect type (Evolve Whole Home Hub with 100A Breaker).

### Evolve Hub Commissioning Quick Guide Installer login account











#### Site Equipment Record

Take pictures as built. Record all equipment serial numbers.